

---

---

# COX

Research and Technology, Inc.

---

---

DUPLEX BLOWER  
CONTROL PANEL  
TAYLOR TRACE

Cox Research and Technology, Inc.  
14697 S. Harrells Ferry Road  
Baton Rouge, LA. 70816  
(225) 756-3271 Fax (225) 755-1030

CP-1860

VOLTAGE	120/240V	(480V, 277/480V, 240V, 120/240V, 208V, 120/208V)
PHASE/HZ	1/60	
NO. MOTORS	2	
HP	5	
FLA	28	
TYPE OF PUMP	Blower	(Self-Priming, Submersible)
MANUFACTURER		
CATALOG NUMBER		
CONTROL VOLTAGE	120V	(120V, Other)
ENCLOSURE	NEMA 4X	(NEMA 1, NEMA 3R, NEMA 4, NEMA 4X)
ENCLOSURE MATERIAL	Fiberglass	(Painted Steel, Stainless Steel, Fiberglass)
CONTROL SENSOR		(Floats, Bubbler, Other)
CAPACITORS		(Yes, No)
CAPACITOR WIRING FIGURE		
THERM. & SEAL FAIL WIRING FIGURE		

OPTIONS:

SEAL FAIL LIGHTS		(Submersible Only)
SEAL FAIL RELAYS		(Submersible Only)
SEAL FAIL PUMP SHUTDOWN		(Submersible Only)
HT PUMP SHUTDOWN		(Self-Primer, Submersible)
ALARM HORN		
ALARM LIGHT		
LIGHT PANEL MTD		
LIGHT REMOTE MTD		
LIGHT FLASHER		
LIGHTNING ARRESTER		
ELAPSED TIME METER		
PHASE MONITOR		
NEMA RATED STARTERS		
GROUND FAULT RECPT.		
GREEN RUN LIGHTS VS. RED		
POLE, BOX, SEAL		
INTRINSICALLY SAFE RELAYS		
HIGH TEMP. LOCKOUT, MANUAL RESET		
ECONOMY VERSION		

SOLD TO: Delta Process Equipment, Inc.

TAG : Taylor Trace


\_\_\_\_\_


SHIP TO: Delta Process Equipment, Inc. - Denham Springs, LA

\_\_\_\_\_

\_\_\_\_\_

	Drawing Title						
	PANEL DESCRIPTION						
DATE		REFERENCE DRAWING	NO.	REVISION-LOCATION	ECN	DATE	BY
8/03/04		S/N	Sales Engineer C.C.	Application Engineer R.C.	DRAWN BY C. RACHAL	APPROVED BY	DATE
	Project Title	<div>COX</div> <div>Research and Technology, Inc.</div>			P.O. Box 77808 Baton Rouge, LA 70809  Ph. (225)756-3271 Fax (225)756-1030		PURCHASE ORDER NUMBER  DRAWING NUMBER CP-1860 SHEET NUMBER 1
	DUPLEX BLOWER CONTROL PANEL						





PANEL IS DESIGNED TO RUN AERATORS WITH A MINIMUM OF 15 MINUTES OF OFF TIME BETWEEN ALTERNATION. PINS PUSHED OUT ON CLOCK INDICATE RUN TIME. PINS PUSHED IN INDICATE OFF TIME. EACH PIN IS EQUAL TO 15 MINUTES.

IF NO OFF TIME IS REQUIRED BETWEEN ALTERNATION, REMOVE JUMPER FROM TERMINALS 5 AND 6 PLACE JUMPER ACROSS TERMINALS 7 AND 8 NOW AERATORS WILL RUN CONTINUOUSLY. SET 1 PIN IN AT THE TIME YOU WISH THE AERATORS TO ALTERNATE. ALL REMAINING PINS SHOULD BE PUSHED OUT.

\* REMOVE JUMPERS AND INSTALL LOCKOUT DEVICES IF REQUIRED


Drawing Title							
CONTROL DIAGRAM							
DATE 8/03/04	REFERENCE DRAWING		NO.		REVISION-LOCATION		ECN
	S/N		Sales Engineer C.C.		Application Engineer R.C.		DATE
Project Title		DRAWN		APPROVED		BY	
DUPLEX BLOWER CONTROL PANEL		BY C. RACHAL				DATE	
		PURCHASE ORDER NUMBER					
		DRAWING NUMBER					
		CP-1860					
		SHEET NUMBER					

**COX**

Research and Technology, Inc.

P.O. Box 77808  
Baton Rouge, LA  
70809


Ph. (225)756-3271  
Fax (225)756-1030



REMOVE JUMPERS & INSTALL  
LOCKOUT DEVICES IF REQUIRED

IF NO OFF TIME IS REQUIRED BETWEEN  
ALTERNATION, REMOVE JUMPER FROM  
TERMINALS ⑤ AND ⑥. PLACE JUMPER ACROSS  
TERMINALS ⑦ AND ⑧. NOW AERATORS WILL RUN  
CONTINUOUSLY. SET 1 PIN IN AT THE TIME YOU  
WISH THE AERATORS TO ALTERNATE.  
ALL REMAINING PINS SHOULD BE PUSHED OUT.

	Drawing Title							
	EXTERNAL CONNECTIONS							
DATE		REFERENCE DRAWING	NO.	REVISION-LOCATION	ECN	DATE	BY	
8/03/04		S/N	Sales Engineer C.C.	Application Engineer R.C.	BY C. RACHAL	APPROVED	BY	DATE
	Project Title	PURCHASE ORDER NUMBER						
	DUPLEX BLOWER CONTROL PANEL	DRAWING NUMBER CP-1860						
		SHEET NUMBER			4			



VIEW OF FRONT OF ENCLOSURE

NOTE:

SEWER GASSES WILL DESTROY COMPONENTS IN PANEL.  
PROPER SEALS MUST BE INSTALLED EXTERNAL TO THE  
PANEL TO PREVENT ENTRY OF GASSES.

NAMEPLATE SCHEDULE

NP-1	BLOWER 1
NP-2	BLOWER 2
NP-3	RUN
NP-4	RUN
NP-5	HOA
NP-6	HOA

DATE 8/03/04	Drawing Title							
	ENCLOSURE							
		REFERENCE DRAWING	NO.	REVISION-LOCATION	ECN	DATE	BY	
	Project Title	S/N	Sales Engineer C.C.	Application Engineer R.C.	BY C. RACHAL	APPROVED	BY	DATE
	DUPLEX BLOWER CONTROL PANEL	<div> <div>COX</div> <div>Research and Technology, Inc.</div> </div>			P.O. Box 77808 Baton Rouge, LA 70809  Ph. (225)756-3271 Fax (225)756-1030		PURCHASE ORDER NUMBER	
							DRAWING NUMBER CP-1860	
							SHEET NUMBER 5	

## BILL OF MATERIAL

ITEM	QTY	MANUFACTURER	PART NO.	DESCRIPTION
1	1	VYNCKIER	VJ1816HWPL	ENCLOSURE
2	1	VYNCKIER	MP1816A	BACKPLATE
3	2	ABB	A40-30-10-84	STARTER
4	2	ABB	TA42DU32	O.L. (22-32A)
5	2	SQUARE D	QOU260	CIRCUIT BREAKER 1,2
6	1	ABB	OT100E3	DISC. SWITCH
7	2	ACI	JR22P3M20B	H.O.A. SWITCH
8	2	ACI	JR22FR	RED PILOT LIGHTS
9	1	TIMEMARK	261DT120	ALTERNATING RELAY
10	1	GRASSLIN	FM/1 STUZH-L	TIMER
11	1	MARATHON	1323580	DISTRIBUTION BLOCK
12				

	Drawing Title										
	BILL OF MATERIALS										
DATE 8/03/04		S/N	Sales Engineer C.C.	Application Engineer R.C.	REFERENCE DRAWING NO.  	REVISION-LOCATION  	ECN  	DATE BY  			
	Project Title							PURCHASE ORDER NUMBER			
	DUPLEX BLOWER CONTROL PANEL	<b>COX</b> Research and Technology, Inc.						P.O. Box 77808 Baton Rouge, LA 70809	DRAWING NUMBER CP-1860		
								Ph. (225)756-3271 Fax (225)756-1030	SHEET NUMBER		6