

---

---

COX

Research and Technology, Inc.

---

---

DUPLEX BLOWER  
CONTROL PANEL  
CARDINAL CONTRACTING  
MOBILE COUNTY  
RIVER DELTA MARINA

Cox Research and Technology, Inc.  
14697 S. Harrells Ferry Road  
Baton Rouge, LA. 70816  
(225) 756-3271 Fax (225) 755-1030

CP-2161

VOLTAGE	<u>120/240V</u>	(480V, 277/480V, 240V, 120/240V, 208V, 120/208V)
PHASE/HZ	<u>1/60</u>	
NO. MOTORS	<u>2</u>	
HP	<u>5</u>	
FLA	<u>28</u>	
TYPE OF PUMP	<u>Blower</u>	(Self-Priming, Submersible)
MANUFACTURER	<u></u>	
CATALOG NUMBER	<u></u>	
CONTROL VOLTAGE	<u>120V</u>	(120V, Other)
ENCLOSURE	<u>NEMA 4X</u>	(NEMA 1, NEMA 3R, NEMA 4, NEMA 4X)
ENCLOSURE MATERIAL	<u>Fiberglass</u>	(Painted Steel, Stainless Steel, Fiberglass)
CONTROL SENSOR	<u></u>	(Floats, Bubbler, Other)
CAPACITORS	<u></u>	(Yes, No)
CAPACITOR WIRING FIGURE	<u></u>	
THERM. & SEAL FAIL WIRING FIGURE	<u></u>	

OPTIONS:


SEAL FAIL LIGHTS	<u></u>	(Submersible Only)
SEAL FAIL RELAYS	<u></u>	(Submersible Only)
SEAL FAIL PUMP SHUTDOWN	<u></u>	(Submersible Only)
HT PUMP SHUTDOWN	<u></u>	(Self-Primer, Submersible)
ALARM HORN	<u></u>	
ALARM LIGHT	<u></u>	
LIGHT PANEL MTD	<u></u>	
LIGHT REMOTE MTD	<u></u>	
LIGHT FLASHER	<u></u>	
LIGHTNING ARRESTER	<u></u>	
ELAPSED TIME METER	<u></u>	
PHASE MONITOR	<u></u>	
NEMA RATED STARTERS	<u></u>	
GROUND FAULT RECPT.	<u></u>	
GREEN RUN LIGHTS VS. RED	<u></u>	
POLE, BOX, SEAL	<u></u>	
INTRINSICALLY SAFE RELAYS	<u></u>	
HIGH TEMP. LOCKOUT, MANUAL RESET	<u></u>	
ECONOMY VERSION	<u></u>	

SOLD TO: Delta Process Equipment, Inc.


TAG : Cardinal Contracting - Mobile County

River Delta Marina

SHIP TO: Delta Process Equipment, Inc. - Denham Springs, LA

	Drawing Title						
	PANEL DESCRIPTION						
DATE 9/22/05		REFERENCE DRAWING S/N	NO. Sales Engineer C.C.	REVISION-LOCATION Application Engineer R.C.	DRAWN BY C. RACHAL	ECN	DATE
	Project Title	<div style="text-align: center;">   <b>COX</b>  Research and Technology, Inc. </div>			P.O. Box 77808 Baton Rouge, LA 70809		PURCHASE ORDER NUMBER
	DUPLEX BLOWER CONTROL PANEL				Ph. (225)756-3271 Fax (225)755-1030		DRAWING NUMBER CP-2161
							SHEET NUMBER 1





PANEL IS DESIGNED TO RUN AERATORS WITH A MINIMUM OF 15 MINUTES OF OFF TIME BETWEEN ALTERNATION. PINS PUSHED OUT ON CLOCK INDICATE RUN TIME. PINS PUSHED IN INDICATE OFF TIME. EACH PIN IS EQUAL TO 15 MINUTES.


IF NO OFF TIME IS REQUIRED BETWEEN ALTERNATION, REMOVE JUMPER FROM TERMINALS 5 AND 6 PLACE JUMPER ACROSS TERMINALS 7 AND 8 NOW AERATORS WILL RUN CONTINUOUSLY. SET 1 PIN IN AT THE TIME YOU WISH THE AERATORS TO ALTERNATE. ALL REMAINING PINS SHOULD BE PUSHED OUT.

\* REMOVE JUMPERS AND INSTALL LOCKOUT DEVICES IF REQUIRED

	Drawing Title								
	CONTROL DIAGRAM								
DATE		REFERENCE DRAWING	NO.	REVISION-LOCATION	ECN	DATE	BY		
9/22/05		S/N	Sales Engineer C.C.	Application Engineer R.C.	DRAWN BY C. RACHAL	APPROVED			
	Project Title							PURCHASE ORDER NUMBER	
	DUPLEX BLOWER CONTROL PANEL							DRAWING NUMBER CP-2161	
								SHEET NUMBER	3

**COX**  
Research and Technology, Inc.


P.O. Box 77808  
Baton Rouge, LA  
70809  
Ph. (225)756-3271  
Fax (225)755-1030



REMOVE JUMPERS & INSTALL  
LOCKOUT DEVICES IF REQUIRED

IF NO OFF TIME IS REQUIRED BETWEEN  
ALTERNATION, REMOVE JUMPER FROM  
TERMINALS ⑤ AND ⑥. PLACE JUMPER ACROSS  
TERMINALS ⑦ AND ⑧. NOW AERATORS WILL RUN  
CONTINUOUSLY. SET 1 PIN IN AT THE TIME YOU  
WISH THE AERATORS TO ALTERNATE.  
ALL REMAINING PINS SHOULD BE PUSHED OUT.

	Drawing Title							
	EXTERNAL CONNECTIONS							
DATE		REFERENCE DRAWING	NO.	REVISION-LOCATION	ECN	DATE	BY	
9/22/05		S/N	Sales Engineer C.C.	Application Engineer R.C.	BY C. RACHAL	APPROVED	BY	DATE
	Project Title				P.O. Box 77808 Baton Rouge, LA 70809	PURCHASE ORDER NUMBER		
	DUPLEX BLOWER CONTROL PANEL	<div>COX</div> <div>Research and Technology, Inc.</div>			Ph. (225)756-3271 Fax (225)755-1030	DRAWING NUMBER CP-2161		
						SHEET NUMBER 4		



VIEW OF FRONT OF ENCLOSURE

NOTE:

SEWER GASSES WILL DESTROY COMPONENTS IN PANEL.  
PROPER SEALS MUST BE INSTALLED EXTERNAL TO THE  
PANEL TO PREVENT ENTRY OF GASSES.

NAMEPLATE SCHEDULE

NP-1	BLOWER 1
NP-2	BLOWER 2
NP-3	RUN
NP-4	RUN
NP-5	HOA
NP-6	HOA

	Drawing Title							
	ENCLOSURE							
DATE 9/22/05		REFERENCE DRAWING S/N	NO. Sales Engineer C.C.	REVISION-LOCATION Application Engineer R.C.	ECN BY C. RACHAL	DATE BY	BY DATE	
	Project Title	<div>COX</div> <div>Research and Technology, Inc.</div>			P.O. Box 77808 Baton Rouge, LA 70809		PURCHASE ORDER NUMBER	
	DUPLEX BLOWER CONTROL PANEL				Ph. (225)756-3271 Fax (225)755-1030		DRAWING NUMBER CP-2161	
							SHEET NUMBER 5	

## BILL OF MATERIAL

ITEM	QTY	MANUFACTURER	PART NO.	DESCRIPTION
1	1	STAHLIN	RJ1614HPL	ENCLOSURE
2	1	STAHLIN	BP1614AL	BACKPLATE
3	2	ABB	A30-30-10-84	STARTER
4	2	ABB	TA25DU32	O.L. (24-32A)
5	2	SQUARE D	QOU260	CIRCUIT BREAKER 1,2
6	1	ABB	OT100E3	DISC. SWITCH
7	2	ACI	JR22P3M20B	H.O.A. SWITCH
8	2	ACI	JR22FR	RED PILOT LIGHTS
9	1	TIMEMARK	261DT120	ALTERNATING RELAY
10	1	GRASSLIN	FM/1 STUZH-L	TIMER
11	1	MARATHON	1323580	DISTRIBUTION BLOCK
12				

[illegible]