
COX

Research and Technology, Inc.

OXBOW GARDENS
DUPLEX BLOWER
CONTROL PANEL

Cox Research and Technology, Inc.
14697 S. Harrells Ferry Road
Baton Rouge, LA. 70816
(225) 756-3271 Fax (225) 755-1030

CP-1844

VOLTAGE	<u>120/240V</u>	(480V, 277/480V, 240V, 120/240V, 208V, 120/208V)
PHASE/HZ	<u>1/60</u>	
NO. MOTORS	<u>2</u>	
HP	<u>2</u>	
FLA	<u>11.6</u>	
TYPE OF PUMP	<u>Blower</u>	(Self-Priming, Submersible)
MANUFACTURER	<u>Sutorbilt</u>	
CATALOG NUMBER	<u></u>	
CONTROL VOLTAGE	<u>120V</u>	(120V, Other)
ENCLOSURE	<u>NEMA 4X</u>	(NEMA 1, NEMA 3R, NEMA 4, NEMA 4X)
ENCLOSURE MATERIAL	<u>Fiberglass</u>	(Painted Steel, Stainless Steel, Fiberglass)
CONTROL SENSOR	<u></u>	(Floats, Bubbler, Other)
CAPACITORS	<u></u>	(Yes, No)
CAPACITOR WIRING FIGURE	<u></u>	
THERM. & SEAL FAIL WIRING FIGURE	<u></u>	

OPTIONS:


SEAL FAIL LIGHTS	<u></u>	(Submersible Only)
SEAL FAIL RELAYS	<u></u>	(Submersible Only)
SEAL FAIL PUMP SHUTDOWN	<u></u>	(Submersible Only)
HT PUMP SHUTDOWN	<u></u>	(Self-Primer, Submersible)
ALARM HORN	<u></u>	
ALARM LIGHT	<u></u>	
LIGHT PANEL MTD	<u></u>	
LIGHT REMOTE MTD	<u></u>	
LIGHT FLASHER	<u></u>	
LIGHTNING ARRESTER	<u></u>	
ELAPSED TIME METER	<u></u>	
PHASE MONITOR	<u></u>	
NEMA RATED STARTERS	<u></u>	
GROUND FAULT RECPT.	<u></u>	
GREEN RUN LIGHTS VS. RED	<u></u>	
POLE, BOX, SEAL	<u></u>	
INTRINSICALLY SAFE RELAYS	<u></u>	
HIGH TEMP. LOCKOUT, MANUAL RESET	<u></u>	
ECONOMY VERSION	<u></u>	

SOLD TO: Delta Process Equipment, Inc.

TAG : OXBOW GARDENS

SHIP TO: Delta Process Equipment, Inc. - Denham Springs, LA

	Drawing Title						
	PANEL DESCRIPTION						
DATE 7/08/04		REFERENCE DRAWING S/N	NO. Sales Engineer C.C.	REVISION-LOCATION Application Engineer R.C.	DRAWN BY C. RACHAL	ECN	DATE
	Project Title	<div style="text-align: center;"> COX Research and Technology, Inc. </div>			P.O. Box 77808 Baton Rouge, LA 70809		PURCHASE ORDER NUMBER
	DUPLEX BLOWER CONTROL PANEL				Ph. (225)756-3271 Fax (225)756-1030		DRAWING NUMBER CP-1844
							SHEET NUMBER 1




PANEL IS DESIGNED TO RUN AERATORS WITH A MINIMUM OF 15 MINUTES OF OFF TIME BETWEEN ALTERNATION. PINS PUSHED OUT ON CLOCK INDICATE RUN TIME. PINS PUSHED IN INDICATE OFF TIME. EACH PIN IS EQUAL TO 15 MINUTES.

IF NO OFF TIME IS REQUIRED BETWEEN ALTERNATION, REMOVE JUMPER FROM TERMINALS ⑤ AND ⑥ PLACE JUMPER ACROSS TERMINALS ⑦ AND ⑧ NOW AERATORS WILL RUN CONTINUOUSLY. SET 1 PIN IN AT THE TIME YOU WISH THE AERATORS TO ALTERNATE. ALL REMAINING PINS SHOULD BE PUSHED OUT.

REMOVE JUMPERS AND INSTALL LOCKOUT DEVICES IF REQUIRED


	Drawing Title <	
--	--	--



REMOVE JUMPERS & INSTALL
LOCKOUT DEVICES IF REQUIRED

IF NO OFF TIME IS REQUIRED BETWEEN
ALTERNATION, REMOVE JUMPER FROM
TERMINALS ⑤ AND ⑥. PLACE JUMPER ACROSS
TERMINALS ⑦ AND ⑧. NOW AERATORS WILL RUN
CONTINUOUSLY. SET 1 PIN IN AT THE TIME YOU
WISH THE AERATORS TO ALTERNATE.
ALL REMAINING PINS SHOULD BE PUSHED OUT.

	Drawing Title								
	EXTERNAL CONNECTIONS								
DATE		REFERENCE DRAWING	NO.	REVISION-LOCATION	ECN	DATE	BY		
7/08/04		S/N	Sales Engineer C.C.	Application Engineer R.C.	BY C. RACHAL	APPROVED			
	Project Title				P.O. Box 77808 Baton Rouge, LA 70809	PURCHASE ORDER NUMBER			
	DUPLEX BLOWER CONTROL PANEL	<div>COX</div> <div>Research and Technology, Inc.</div>			Ph. (225)756-3271 Fax (225)756-1030	DRAWING NUMBER CP-1844			
						SHEET NUMBER 4			



VIEW OF FRONT OF ENCLOSURE

NOTE:
SEWER GASSES WILL DESTROY COMPONENTS IN PANEL.
PROPER SEALS MUST BE INSTALLED EXTERNAL TO THE
PANEL TO PREVENT ENTRY OF GASSES.

NAMEPLATE SCHEDULE

NP-1	BLOWER 1
NP-2	BLOWER 2
NP-3	RUN
NP-4	RUN
NP-5	HOA
NP-6	HOA

DATE 7/08/04	Drawing Title							
	ENCLOSURE							
		REFERENCE DRAWING	NO.	REVISION-LOCATION	ECN	DATE	BY	
	Project Title	S/N	Sales Engineer C.C.	Application Engineer R.C.	DRAWN BY C. RACHAL	APPROVED BY	DATE	PURCHASE ORDER NUMBER
	DUPLEX BLOWER CONTROL PANEL	<div style="text-align: center;"> COX Research and Technology, Inc. </div>			P.O. Box 77808 Baton Rouge, LA 70809	DRAWING NUMBER CP-1844		
					Ph. (225)756-3271 Fax (225)756-1030	SHEET NUMBER 5		

BILL OF MATERIAL

ITEM	QTY	MANUFACTURER	PART NO.	DESCRIPTION
1	1	VYNCKIER	VJ1816HWPL	ENCLOSURE
2	1	VYNCKIER	MP1816A	BACKPLATE
3	2	ABB	A16-30-10-84	STARTER
4	2	ABB	TA25DU14	O.L. (10-14A)
5	2	SQUARE D	QOU225	CIRCUIT BREAKER 1,2
6	1	ABB	OT63E3	DISC. SWITCH
7	2	ACI	JR22P3M20B	H.O.A. SWITCH
8	2	ACI	JR22FR	RED PILOT LIGHTS
9	1	TIMEMARK	261DT120	ALTERNATING RELAY
10	1	GRASSLIN	FM/1 STUZH-L	TIMER
11	1	MARATHON	1323580	DISTRIBUTION BLOCK
12				

	Drawing Title						
	<h2 style="margin: 0;">BILL OF MATERIALS</h2>						
DATE 7/08/04		REFERENCE DRAWING	NO.	REVISION-LOCATION	ECN	DATE	BY
		S/N	Sales Engineer C.C.	Application Engineer R.C.	DRAWN BY C. RACHAL	APPROVED BY	DATE
	Project Title	<div style="border-top: 3px double black; border-bottom: 3px double black; padding: 5px;"> <h1 style="margin: 0;">COX</h1> <p style="margin: 0;">Research and Technology, Inc.</p> </div>			P.O. Box 77808 Baton Rouge, LA 70809 Ph. (225)756-3271 Fax (225)756-1030		PURCHASE ORDER NUMBER DRAWING NUMBER <div style="text-align: right;">CP-1844</div> SHEET NUMBER <div style="text-align: right;">6</div>
	DUPLEX BLOWER CONTROL PANEL						