



NOTE:
SEWER GASSES WILL DESTROY COMPONENTS IN PANEL.
PROPER SEALS MUST BE INSTALLED EXTERNAL TO THE
PANEL TO PREVENT ENTRY OF GASSES.

NAMEPLATE SCHEDULE

NP-1	PUMP 1	NP-9	PUMP FAIL
NP-2	PUMP 2	NP-10	PUMP FAIL
NP-3	RUN	NP-11	PUMP FAIL RESET
NP-4	RUN	NP-12	HIGH WATER
NP-5	HOA	NP-13	TRANSDUCER/FLOATS
NP-6	HOA	NP-14	P1-ALT-P2
NP-7	SOFT START FAULT		
NP-8	SOFT START FAULT		

	Drawing Title							
	ENCLOSURE		1	LIGHTNING ARRESTER		5/30/06	TL	
DATE		REFERENCE DRAWING	NO.	REVISION-LOCATION	ECN	DATE	BY	
3/29/06		S/N	Sales Engineer C.C.	Application Engineer R.C.	DRAWN BY C. RACHAL	APPROVED BY	DATE	
	Project Title	COX			P.O. Box 77808 Baton Rouge, LA 70809	PURCHASE ORDER NUMBER		
	DUPLEX PUMP CONTROL PANEL	Research and Technology, Inc.			Ph. (225)756-3271 Fax (225)755-1030	DRAWING NUMBER CP-2205		
						SHEET NUMBER 5		