
COX

Research and Technology, Inc.

TREATMENT PLANT
DUPLEX BLOWER
CONTROL PANEL
LAKE CATHERINE

Cox Research and Technology, Inc.
14697 S. Harrells Ferry Road
Baton Rouge, LA. 70816
(225) 756-3271 Fax (225) 755-1030

CP-1707

VOLTAGE	<u>120/240V</u>	(480V, 277/480V, 240V, 120/240V, 208V, 120/208V)
PHASE/HZ	<u>1/60</u>	
NO. MOTORS	<u>2, 1</u>	
HP	<u>5, 3/4</u>	
FLA	<u>28, 5A</u>	
TYPE OF PUMP	<u>Blower, Pump</u>	(Self-Priming, Submersible)
MANUFACTURER	<u></u>	
CATALOG NUMBER	<u></u>	
CONTROL VOLTAGE	<u>120V</u>	(120V, Other)
ENCLOSURE	<u>NEMA 4X</u>	(NEMA 1, NEMA 3R, NEMA 4, NEMA 4X)
ENCLOSURE MATERIAL	<u>Fiberglass</u>	(Painted Steel, Stainless Steel, Fiberglass)
CONTROL SENSOR	<u></u>	(Floats, Bubbler, Other)
CAPACITORS	<u></u>	(Yes, No)
CAPACITOR WIRING FIGURE	<u></u>	
THERM. & SEAL FAIL WIRING FIGURE	<u></u>	


OPTIONS:


SEAL FAIL LIGHTS	<u></u>	(Submersible Only)
SEAL FAIL RELAYS	<u></u>	(Submersible Only)
SEAL FAIL PUMP SHUTDOWN	<u></u>	(Submersible Only)
HT PUMP SHUTDOWN	<u></u>	(Self-Primer, Submersible)
ALARM HORN	<u></u>	
ALARM LIGHT	<u></u>	
LIGHT PANEL MTD	<u></u>	
LIGHT REMOTE MTD	<u></u>	
LIGHT FLASHER	<u></u>	
LIGHTNING ARRESTER	<u></u>	
ELAPSED TIME METER	<u></u>	
PHASE MONITOR	<u></u>	
NEMA RATED STARTERS	<u></u>	
GROUND FAULT RECPT.	<u></u>	
GREEN RUN LIGHTS VS. RED	<u></u>	
POLE, BOX, SEAL	<u></u>	
INTRINSICALLY SAFE RELAYS	<u></u>	
HIGH TEMP. LOCKOUT, MANUAL RESET	<u></u>	
ECONOMY VERSION	<u></u>	

SOLD TO: Delta Process Equipment, Inc.


TAG : LAKE CATHERINE TREATMENT PLANT

SHIP TO: Delta Process Equipment, Inc. - Ruston, LA

	Drawing Title						
	PANEL DESCRIPTION						
DATE 12/08/03		REFERENCE DRAWING S/N	NO. Sales Engineer C.C.	REVISION-LOCATION Application Engineer R.C.	DRAWN BY C. RACHAL	ECN	DATE
	Project Title	<div style="text-align: center;">  COX Research and Technology, Inc. </div>			P.O. Box 77808 Baton Rouge, LA 70809		PURCHASE ORDER NUMBER
	DUPLEX BLOWER CONTROL PANEL				Ph. (225)756-3271 Fax (225)756-1030		DRAWING NUMBER CP-1707
							SHEET NUMBER 1



	Drawing Title							
	POWER DIAGRAM							
DATE 12/08/03		REFERENCE DRAWING S/N	NO. Sales Engineer C.C.	REVISION-LOCATION Application Engineer R.C.	DRAWN BY C. RACHAL	ECN	DATE	BY
	Project Title	PURCHASE ORDER NUMBER			APPROVED			
	DUPLEX BLOWER CONTROL PANEL	DRAWING NUMBER CP-1707			DATE			
		SHEET NUMBER			2			




PANEL IS DESIGNED TO RUN BLOWERS WITH A MINIMUM OF 15 MINUTES OF OFF TIME BETWEEN ALTERNATION. PINS PUSHED OUT ON CLOCK INDICATE RUN TIME. PINS PUSHED IN INDICATE OFF TIME. EACH PIN IS EQUAL TO 15 MINUTES.


IF NO OFF TIME IS REQUIRED BETWEEN ALTERNATION, REMOVE JUMPER FROM TERMINALS ⑤ AND ⑥ PLACE JUMPER ACROSS TERMINALS ⑦ AND ⑧ NOW BLOWERS WILL RUN CONTINUOUSLY. SET 1 PIN IN AT THE TIME YOU WISH THE BLOWERS TO ALTERNATE. ALL REMAINING PINS SHOULD BE PUSHED OUT.

* REMOVE JUMPERS AND INSTALL LOCKOUT DEVICES IF REQUIRED

	Drawing Title CONTROL DIAGRAM									
DATE 12/08/03			REFERENCE DRAWING		NO.	REVISION-LOCATION		ECN	DATE	BY
			S/N	Sales Engineer C.C.	Application Engineer R.C.	DRAWN BY C. RACHAL		APPROVED BY DATE		
	Project Title		<div>COX</div> <div>Research and Technology, Inc.</div>			P.O. Box 77808 Baton Rouge, LA 70809 Ph. (225)756-3271 Fax (225)756-1030		PURCHASE ORDER NUMBER		
	DUPLEX BLOWER CONTROL PANEL							DRAWING NUMBER CP-1707		
								SHEET NUMBER		
								3		



IF NO OFF TIME IS REQUIRED BETWEEN
ALTERNATION, REMOVE JUMPER FROM
TERMINALS ⑤ AND ⑥. PLACE JUMPER ACROSS
TERMINALS ⑦ AND ⑧. NOW BLOWERS WILL RUN
CONTINUOUSLY. SET 1 PIN IN AT THE TIME YOU
WISH THE BLOWERS TO ALTERNATE.
ALL REMAINING PINS SHOULD BE PUSHED OUT.



VIEW OF FRONT OF ENCLOSURE

NOTE:

SEWER GASSES WILL DESTROY COMPONENTS IN PANEL.
PROPER SEALS MUST BE INSTALLED EXTERNAL TO THE
PANEL TO PREVENT ENTRY OF GASSES.


NAMEPLATE SCHEDULE

NP-1	BLOWER 1
NP-2	BLOWER 2
NP-3	RUN
NP-4	RUN
NP-5	HOA
NP-6	HOA
NP-7	SLUDGE RETURN PUMP
NP-8	RUN
NP-9	OFF-ON

DATE 12/08/03	Drawing Title							
	ENCLOSURE							
		REFERENCE DRAWING	NO.	REVISION-LOCATION	ECN	DATE	BY	
		S/N	Sales Engineer C.C.	Application Engineer R.C.	BY C. RACHAL	APPROVED	DATE	
	Project Title				P.O. Box 77808 Baton Rouge, LA 70809	PURCHASE ORDER NUMBER		
	DUPLEX BLOWER CONTROL PANEL	<div>COX</div> <div>Research and Technology, Inc.</div>			Ph. (225)756-3271 Fax (225)756-1030	DRAWING NUMBER CP-1707		
						SHEET NUMBER 5		

BILL OF MATERIAL

ITEM	QTY	MANUFACTURER	PART NO.	DESCRIPTION
1	1	VYNCKIER	VJ1816HWPL	ENCLOSURE
2	1	VYNCKIER	MP1816AL	BACKPLATE
3	2	ABB	A26-30-10-84	STARTER 1,2
4	2	ABB	TA25DU32	O.L. (24-32A)
5	2	SQUARE D	QOU260	CIRCUIT BREAKER 1,2
6	1	MARATHON	1323580	DISTRIBUTION BLOCK
7	2	ACI	JR22P3M20B	H.O.A. SWITCH
8	3	ACI	JR22FR	RED PILOT LIGHTS
9	1	TIMEMARK	261DT120	ALTERNATING RELAY
10	1	BUSSMAN	LP-CC-5	FUSE 5.0A
11	1	DIEHL	TA-4152	TIMER W/BATT BACK UP
12	1	MARATHON	6SC30A-1I	FUSE HOLDER
9	1	ABB	A16-30-10-84	STARTER 3
10	1	ABB	TA25DU6.5	O.L. (4.5-6.5A)
11	1	SQUARE D	QOU215	CB3
12	1	ACI	JR22P2M11B	OFF-ON SWITCH

	Drawing Title									
	BILL OF MATERIALS									
DATE 12/08/03		REFERENCE DRAWING S/N	NO. Sales Engineer C.C.	REVISION-LOCATION Application Engineer R.C.	ECN BY C. RACHAL	DATE BY	BY DATE			
	Project Title					P.O. Box 77808 Baton Rouge, LA 70809	PURCHASE ORDER NUMBER			
	DUPLEX BLOWER CONTROL PANEL	<div style="text-align: center;">  <p>Research and Technology, Inc.</p> </div>				Ph. (225)756-3271 Fax (225)756-1030	DRAWING NUMBER CP-1707			
							SHEET NUMBER 6			